

Mundelein Fire Department Fire Alarm Requirements

- Required on all new construction
- Must be designed Licensed Engineer
- Three set of prints are required, with cut sheets and battery calculations
- There is a plan review fee, of \$100.00, plus \$1.00 per device.
- A fully functional annunciator panel is required by front door
- Zone map is required by annunciator panel and fire alarm panel
- Duct detectors shall send a full fire signal
- Duct detectors shall reset through panel
- Roof top units shall be identified to correlate with the duct detector
- Battery backup for system can be 24 hours
- AES Keltron Radio shall send a trouble, supervisory signal, and full alarm
- Signals shall go to the Mundelein Dispatch Center
- Knox Box shall not have a tamper switch installed in it
- Call ahead 24 to 48 hours for test

If you need further information please email

fdbureau@mundelein.org

They will get back to you as soon as possible

