<u>Mundelein Fire Department Hood and Duct System</u> <u>Requirements</u>

- A UL 300 compliant system shall be installed
- Plans with cut sheets shall be presented for review
- Contact the Fire Prevention Bureau to witness the test
- System shall be connected to the fire alarm system if the occupancy is equipped with one
- Pull station shall be 10' away and in the direction of egress
- Gas shall turn off when activated
- Any electrical outlets under the hoods shall turn off if system is activated
- A class "K" extinguisher is required
- A plan review fee of \$75.00 per hood applies.

If you need further information please email

fdbureau@mundelein.org

They will get back to you as soon as possible